

TDR Projects Limited: Case Study

TDR Projects Limited was engaged to undertake the new roof installation on this newly demolish and rebuilt building on behalf of Morrow & Jones Construction.

Front Elevation



Front Elevation

Originally a semi-detached property, the client's half was demolished and replaced with a newly built detached structure by Morrow & Jones, incorporating high-quality traditional materials. The roofing works included installing 3,500 new Welsh 16x10 slates over counter battens (cold roof system) on the main building and 800 slates on the garage. Five Velux roof lights were fitted, along with step flashings and lead valleys. The project also featured 45 collared ridge tiles and new OG cast iron gutters, fixed to the brick corbelling to complement the building's classic design.

TDR Projects Limited: Case Study

Programme: 3 weeks

Type: Labour & plant

Completion: On schedule.

Aerial View



0

Reported snags or defects

0

Reported Safety incidents

0

Variations / changes



Side Elevation



Garage Roof and front elevation



Rear Elevation – during construction



Front elevation – Cold roof system



Rear Elevation – During construction